



## THE DIGITAL MALAWI PROGRAM PHASE I: DIGITAL FOUNDATIONS PROJECT

PROJECT NUMBER:

P160533

Upgrade and Installation of Local Area Network (LAN) in selected Government Buildings (Lilongwe and Salima)

### Response to Queries

QUERIES RELATED THE DIGITAL MALAWI PROGRAM PHASE I: DIGITAL FOUNDATIONS PROJECT	
Query	Responses
Preferred Cable brand	Bidders are advised to propose
There is no CAT6e- Confirm if its CAT6 or CAT6a	Cat6 - specific cat6 bidder propose as long as is compatible with equipment they deploy
Number of points per Floor (UTP cable length 305m X 5 can install 25-30 points per floor)	Proposed solution is wireless.
How many fibre cores for the uplink 4core or 8core	Bidders are advised to propose
Fibre Accessories (Fibre Patch panels and patch cords)	Bidders are advised to propose
Fibre connection type (LC/ST/SC)- Proposing LC	Bidders are advised to Propose
CAT6 UTP patch panel not included	Bidders are advised to include the CAT6 UTP patch panel
Cable Spiral Wrap size?	Bidders are advised to propose
4U cabinet is insufficient to accommodate passive and active equipment (Proposing 12U or 15U Swing frame wall mount) refer to the picture below.	That's fine. Bidders may use what works for their equipment and configuration.